



# Forest Reefs and Tallwood Roads Intersection

Status: Works commencing early February

Estimated Completion Date: April 2024

Funding:

- \$560,683 - NSW Government Resources for Regions Round 8
- \$150,000 - NSW Government Resources for Regions Round 9
- \$202,418 - NSW Government Regional Emergency Road Repair Fund
- \$442,897 - Blayney Shire Council
- \$1,355,998 - Total Project

**Project Description:** These works will primarily involve stabilising the existing road, followed by the laying and compaction of gravel, and sealing. The project will also include replacement of the existing kerb and gutter, renewal of existing stormwater infrastructure, and removal of the concrete islands. The extent of works is shown over the page.

This intersection upgrade will increase the safety of the intersection through the inclusion of turning lanes and new linemarking. The renewed stormwater infrastructure will help reduce the impact of water ponding in the intersection.



